



NOTES:

1. FOR INSTALLATION SHOWN ON DRAWING WHERE WATER TABLE (AT SEASONAL HIGH) IS ABOVE BASE OF DRAIN ROCK, INSERT THREADED PLUGS IN DRAIN HOLES AND SUBSTITUTE GRANULAR PIPE BEDDING FOR DRAIN ROCK. (COMPACT PIPE BEDDING TO 95% MODIFIED PROCTOR DENSITY)

(N.T.S.)

CITY OF NORTH VANCOUVER

HYDRANT ASSEMBLY

DRAWN: JN

DATE: JANUARY 2019

DWG.No. **W4R**

CHECKED: M.TRINKLE

APPROVED: DTM